



- Proposed 400kV line
- Existing 132kV lines to be removed

Measures include:

- 1** A total of **6km** from sections of three 132kV overhead transmission lines connecting into Beaulieu substation to be removed and replaced with underground cables
 - 2** **40km** of 132kV overhead transmission line between Etteridge and Boat of Garten in the Cairngorms National Park to be removed and replaced with 33kV overhead lines supported by wooden poles, or underground cables
 - 3** **53km** of 132kV overhead transmission line between Boat of Garten and Cairnmore in the Cairngorms National Park to be removed completely
- Within the central area of the Cairngorms National Park, a total of 128km of existing transmission line will be removed and 28km of new line installed running close to the western boundary of the Park
- 4** Removal of a **3km** section of 132kV overhead transmission line around Whitebridge
 - 5** Removal of a **7km** section of 132kV overhead transmission line around Amulree